

OSCAR Bioenergy Joint Venture

Contract No. EP/SP/61/10
Organic Resources Recovery
Centre (Phase 1):
*Seventy-ninth Monthly EM&A
Report*

1 December 2021 - 31 December 2021

Environmental Resources Management

2509, 25/F, One Harbourfront,
18 Tak Fung Street,
Hung Hom, Kowloon, Hong Kong
Telephone: (852) 2271 3000
Facsimile: (852) 3015 8052
E-mail: post.hk@erm.com
<http://www.erm.com>

Meinhardt Infrastructure and Environment Limited

**Organic Resources Recovery Centre,
Phase I**

Monthly EM&A Report

(1 December 2021 – 31 December 2021)

(October 2022)

Verified by: Claudine Lee



Position: Independent Environmental Checker


Date: 3rd October 2022

OSCAR Bioenergy Joint Venture

Contract No. EP/SP/61/10
Organic Resources Recovery
Centre (Phase 1):
*Seventy-ninth Monthly EM&A
Report*

1 December 2021 - 30 December 2021

Reference 0279222

| | |
|---|--|
| For and on behalf of ERM-Hong Kong, Limited | |
| Approved by: | Frank Wan |
| Signed: |  |
| Position: | Partner |
| Certified by: |  (Environmental Team Leader - Mandy To) |
| Date: | 22 August 2022 (Rev.1) |

CONTENTS

EXECUTIVE SUMMARY

| | | |
|-------|--|----|
| 1 | INTRODUCTION | 1 |
| 1.1 | PURPOSE OF THE REPORT | 1 |
| 1.2 | STRUCTURE OF THE REPORT | 1 |
| 2 | PROJECT INFORMATION | 3 |
| 2.1 | BACKGROUND | 3 |
| 2.2 | GENERAL SITE DESCRIPTION | 4 |
| 2.3 | MAJOR ACTIVITIES UNDERTAKEN | 4 |
| 2.4 | PROJECT ORGANISATION AND MANAGEMENT STRUCTURE | 4 |
| 2.5 | STATUS OF ENVIRONMENTAL APPROVAL DOCUMENTS | 4 |
| 3 | ENVIRONMENTAL MONITORING AND AUDIT REQUIREMENTS | 5 |
| 3.1 | ENVIRONMENTAL MONITORING | 5 |
| 3.1.1 | <i>Air Quality</i> | 5 |
| 3.1.2 | <i>Odour</i> | 7 |
| 3.2 | SITE AUDIT | 9 |
| 3.2.1 | <i>Water Quality</i> | 10 |
| 3.2.2 | <i>Landscape and Visual</i> | 11 |
| 4 | MONITORING RESULTS | 12 |
| 4.1 | AIR QUALITY | 12 |
| 4.1.1 | <i>Commissioning Phase Monitoring</i> | 12 |
| 4.1.2 | <i>Operation Phase Monitoring</i> | 12 |
| 4.2 | ODOUR | 14 |
| 4.2.1 | <i>Operation Phase Monitoring</i> | 14 |
| 4.3 | WATER QUALITY | 15 |
| 4.3.1 | <i>Operation Phase Monitoring</i> | 15 |
| 4.4 | WASTE MANAGEMENT | 16 |
| 4.4.1 | <i>Operation Phase Monitoring</i> | 16 |
| 5 | SITE AUDIT | 17 |
| 5.1 | ENVIRONMENTAL SITE AUDIT | 17 |
| 5.1.1 | <i>Operation Phase</i> | 17 |
| 5.2 | LANDSCAPE AND VISUAL AUDIT | 17 |
| 6 | ENVIRONMENTAL NON-CONFORMANCE AND DEFICIENCIES | 18 |
| 6.1 | SUMMARY OF ENVIRONMENTAL NON-COMPLIANCE AND DEFICIENCIES | 18 |
| 6.2 | SUMMARY OF ENVIRONMENTAL COMPLAINT | 18 |
| 6.3 | SUMMARY OF ENVIRONMENTAL SUMMON AND SUCCESSFUL PROSECUTION | 18 |
| 7 | FUTURE KEY ISSUES | 19 |

| | | |
|-----|--|----|
| 7.1 | <i>KEY ISSUES FOR THE COMING MONTH</i> | 19 |
| 8 | <i>CONCLUSIONS</i> | 20 |

LIST OF TABLES

| | |
|-------------------|---|
| <i>TABLE 2.1</i> | <i>SUMMARY OF ACTIVITIES UNDERTAKEN IN THE REPORTING PERIOD</i> |
| <i>TABLE 2.2</i> | <i>SUMMARY OF ENVIRONMENTAL LICENSING, NOTIFICATION AND PERMIT STATUS</i> |
| <i>TABLE 3.1</i> | <i>SAMPLING AND LABORATORY ANALYSIS METHODOLOGY</i> |
| <i>TABLE 3.2</i> | <i>EMISSION LIMIT FOR CAPCS STACK</i> |
| <i>TABLE 3.3</i> | <i>EMISSION LIMIT FOR CHP STACK</i> |
| <i>TABLE 3.4</i> | <i>EMISSION LIMIT FOR ASP STACK</i> |
| <i>TABLE 3.5</i> | <i>EMISSION LIMIT FOR STANDBY FLARING GAS UNIT ()</i> |
| <i>TABLE 3.6</i> | <i>ODOUR INTENSITY LEVEL</i> |
| <i>TABLE 3.7</i> | <i>ACTION AND LIMIT LEVELS FOR ODOUR NUISANCE</i> |
| <i>TABLE 3.8</i> | <i>EVENT AND ACTION PLAN FOR ODOUR MONITORING</i> |
| <i>TABLE 3.9</i> | <i>DISCHARGE LIMITS FOR EFFLUENT FROM THE EFFLUENT STORAGE TANK</i> |
| <i>TABLE 3.10</i> | <i>DISCHARGE LIMITS FOR EFFLUENT FROM THE PETROL INTERCEPTORS</i> |
| <i>TABLE 4.1</i> | <i>HOURLY AVERAGE OF PARAMETERS RECORDED FOR CAPCS</i> |
| <i>TABLE 4.2</i> | <i>HOURLY AVERAGE OF PARAMETERS RECORDED FOR CHP 1</i> |
| <i>TABLE 4.3</i> | <i>HOURLY AVERAGE OF PARAMETERS RECORDED FOR CHP 2</i> |
| <i>TABLE 4.4</i> | <i>HOURLY AVERAGE OF PARAMETERS RECORDED FOR CHP 3</i> |
| <i>TABLE 4.5</i> | <i>HOURLY AVERAGE OF PARAMETERS RECORDED FOR ASP</i> |
| <i>TABLE 4.6</i> | <i>RESULTS OF THE DISCHARGE SAMPLE FROM THE EFFLUENT STORAGE TANK</i> |
| <i>TABLE 4.7</i> | <i>RESULTS OF THE DISCHARGE SAMPLE FROM THE PETROL INTERCEPTOR 1</i> |
| <i>TABLE 4.8</i> | <i>RESULTS OF THE DISCHARGE SAMPLE FROM THE PETROL INTERCEPTOR 2</i> |
| <i>TABLE 4.9</i> | <i>QUANTITIES OF WASTE GENERATED FROM THE OPERATION OF THE PROJECT</i> |
| <i>TABLE 8.1</i> | <i>EXCEEDANCES FOR STACK EMISSIONS</i> |
| <i>TABLE 8.2</i> | <i>EXCEEDANCES FOR PETROL INTERCEPTOR 2</i> |

LIST OF ANNEXES

| | |
|----------------|---|
| <i>ANNEX A</i> | <i>LOCATION OF PROJECT</i> |
| <i>ANNEX B</i> | <i>PROJECT ORGANISATION CHART AND CONTACT DETAIL</i> |
| <i>ANNEX C</i> | <i>IMPLEMENTATION SCHEDULE OF MITIGATION MEASURES</i> |
| <i>ANNEX D</i> | <i>WASTE FLOW TABLE</i> |
| <i>ANNEX E</i> | <i>ENVIRONMENTAL COMPLAINT, ENVIRONMENTAL SUMMONS AND PROSECUTION LOG</i> |
| <i>ANNEX F</i> | <i>INVESTIGATION REPORT</i> |

EXECUTIVE SUMMARY

The construction works of *No. EP/SP/61/10 Organic Resources Recovery Centre Phase 1 (the Project)* commenced on 21 May 2015. This is the 79th monthly Environmental Monitoring and Audit (EM&A) report presenting the EM&A works carried out during the period from 1 to 31 December 2021 in accordance with the EM&A Manual. Substantial completion of the construction works was confirmed on 3 December 2018. In the meantime, the operation phase EM&A programme had commenced in March 2019. Substantial Completion in respect of substantial part of the Works was confirmed on 24 February 2020. The construction phase EM&A programme was completed in the end of February 2020.

Summary of Works undertaken during the Reporting Month

Works undertaken in the reporting month included:

- Operation of the Project, including organic waste reception, and operation of the pre-treatment facilities, anaerobic digesters, composting facilities, air pollution control systems, on-line emission monitoring system for the Centralised Air Pollution Control Unit (CAPCS), Co-generation Units (CHP)s and Ammonia Stripping Plant (ASP), and the wastewater treatment plant; and
- Fine tuning of the CHPs and modification of the ASP to control the air emission.

Environmental Monitoring and Audit Progress

Air Quality Monitoring

Exceedances on SO₂ from CHP and NO_x, SO₂, VOCs and NH₃ from ASP were recorded on the on-line monitoring system. It should be noted that measurements recorded under abnormal operating conditions, e.g. start up and stopping of stacks, unstable operation, test runs and interference of sensor, are disregarded.

Non-compliance of emission limits from the CHP and ASP was recorded during this reporting period. The exceedances of NO_x, VOCs and NH₃ from ASP occurred due to system instability caused by blockage of the stripping column. To ensure stripping efficiency and stable operation of the ASP, the Contractor has arranged acid-clearing of the blockage in January 2022 and the cleaning of the packaging in the future. The exceedances of SO₂ from the de-sulphurisation system of the CHP and ASP were caused by blockage of the hot water system, which was unblocked as soon as the issue was identified.

The Contractor is also recommended to closely monitor the processes of the modification of the ASP and the post-modification monitoring of emission level to avoid any exceedance. As the issues for the ASP has re-occurred for sometimes, the Contractor is advised to undertake a comprehensive review of

the operation of the concerned systems and the effectiveness of the existing mitigation measures and proposed further measures to avoid the exceedance.

Water Quality

Non-compliance of discharge limit of Suspended Solids and Chemical Oxygen Demand, stipulated in the discharge licence issued by the EPD under the *Water Pollution Control Ordinance*, from Petrol Interceptor 2 was recorded during the reporting period. The Contractor suspected the exceedance to have resulted from the washing down of food waste residue from the ad-hoc unloading and unpacking of food waste near the sampling point between mid-November 2021 and early December 2021. The Contractor has scheduled cleaning of the Petrol Interceptor in January 2022 and will schedule routine cleaning after future ad-hoc pre-processing work on site.

Waste Management

Waste generated from the operation of the Project includes chemical waste, waste generated from pre-treatment process and general refuse.

No chemical waste was collected by licenced waste collector from the operation of the Project.

392.44 tonnes of waste generated from pre-treatment process from the operation of the Project was disposed of at landfill. Among the recyclable waste generated from pre-treatment process from the operation of the Project, 0.00 tonne of metals, 0.67 tonnes of papers/ cardboard packing and 0.00 tonne of plastics were sent to recyclers for recycling during the reporting period.

Around 2.53 tonnes of general refuse from the operation of the Project was disposed of at landfill. Among the recycled general refuse from the operation of the Project, 0.00 tonne of metals, 0.00 tonne of papers/ cardboard packing and 0.00 tonne of plastics were sent to recyclers for recycling during the reporting period.

Findings of Environmental Site Audit

A summary of the monitoring activities undertaken in this reporting period is listed below:

- Joint Environmental Site Inspections 1 time

1 monthly joint environmental site inspection was carried out by the representatives of the Contractor and the MT. The IEC was also present at the joint inspections on 10 December 2021. The environmental control/mitigation measures (related to air quality, water quality, waste (including land contamination prevention), hazard-to-life and landscape and visual) recommended in the approved EIA Report and the EM&A Manual were properly implemented by the Contractor during the reporting month.

Environmental Exceedance/Non-conformance/Compliant/Summons and Prosecution

Exceedances for the air emission limits for the CHP and ASP stacks were recorded during the reporting period.

No complaint/ summon/prosecution was received in this reporting period.

Future Key Issues

Activities to be undertaken in the next reporting month include:

- Operation of the Project.
- Fine tuning of the CHPs and modification of the ASP to control the air emission.

ERM-Hong Kong, Limited (ERM) was appointed by OSCAR Bioenergy Joint Venture (the Contractor) as the Environmental Team (ET) to undertake the construction Environmental Monitoring and Audit (EM&A) programme for the *Contract No. EP/SP/61/10 of Organic Waste Treatment Facilities Phase I*, which the project name has been updated to *Organic Resources Recovery Centre (Phase I) (the Project)* since November 2017. ERM was also appointed by the Contractor to undertake the operation EM&A programme starting 1 March 2019.

1.1 PURPOSE OF THE REPORT

This is the 79th EM&A report which summarises the monitoring results and audit findings for the EM&A programme during the reporting period from 1 to 31 December 2021.

1.2 STRUCTURE OF THE REPORT

The structure of the report is as follows:

Section 1: Introduction

It details the scope and structure of the report.

Section 2: Project Information

It summarises the background and scope of the Project, site description, project organisation and status of the Environmental Permits (EP)/licences.

Section 3: Environmental Monitoring and Audit Requirements

It summarises the environmental monitoring requirements including monitoring parameters, programmes, methodologies, frequency, locations, Action and Limit Levels, Event/Action Plans, as well as environmental audit requirements as recommended in the EM&A Manual and approved EIA report.

Section 4: Monitoring Results

It summarises monitoring results of the reporting period.

Section 5: Site Audit

It summarises the audit findings of the environmental as well as landscape and visual site audits undertaken within the reporting period.

Section 6: Environmental Non-conformance

It summarises any exceedance of environmental performance standard, environmental complaints and summons received within the reporting period.

Section 7: Further Key Issues

It summarises the impact forecast for the next reporting month.

Section 8: Conclusions

2.1

BACKGROUND

The Organic Resources Recovery Centre (ORRC) Phase I development (hereinafter referred to as “the Project”) is to design, construct and operate a biological treatment facility with a capacity of about 200 tonnes per day and convert source-separated organic waste from commercial and industrial sectors (mostly food waste) into compost and biogas through proven biological treatment technologies. The location of the Project site is shown in *Annex A*.

The environmental acceptability of the construction and operation of the Project had been confirmed by findings of the associated Environmental Impact Assessment (EIA) Study completed in 2009. The Director of Environmental Protection (DEP) approved this EIA Report under the *Environmental Impact Assessment Ordinance* (EIAO) (Cap. 499) in February 2010 (Register No.: AEIAR-149/2010) (hereafter referred to as the approved EIA Report). Subsequent Report on Re-assessment on Environmental Implications and Report on Re-assessment on Hazard to Life Implications were completed in 2013, respectively.

An Environmental Permit (EP) (No. EP-395/2010) was issued by the DEP to the EPD (Project Team), the Permit Holder, on 21 June 2010 and varied on 18 March 2013 (No. EP-395/2010/A) and 21 May 2013 (No. EP-395/2010/B), respectively. The Design Build and Operate Contract for the ORRC Phase 1 (Contract No. EP/SP/61/10 Organic Resources Recovery Centre (Phase 1) (the Contract)) was awarded to SITA Waste Services Limited, ATAL Engineering Limited and Ros-Roca, Sociedad Anonima jointly trading as the OSCAR Bioenergy Joint Venture (OSCAR or the Contractor). A Further EP (No. FEP-01/395/2010/B) was issued by the DEP to the OSCAR on 16 February 2015. Variation to both EPs (Nos. EP-395/2010/B and FEP-01/395/2010/B) were made in December 2015. The latest EPs, Nos. EP-395/2010/C and FEP-01/395/2010/C, were issued by the DEP on 21 December 2015.

Under the requirements of Condition 5 of the EP (No. FEP-01/395/2010/C), an Environmental Monitoring and Audit (EM&A) programme as set out in the approved EM&A Manual (hereinafter referred to as EM&A Manual) is required to be implemented during the construction and operation of the Project. ERM-Hong Kong, Ltd (ERM) has been appointed by OSCAR as the Environmental Team (ET) for the construction phase EM&A programme and the Monitoring Team (MT) for the operation phase EM&A programme for the implementation of the EM&A programme in accordance with the requirements of the EP and the approved EM&A Manual.

The construction works commenced on 21 May 2015. The construction phase EM&A programme was completed in the end of February 2020. The

operation phase of the EM&A programme commenced on 1 March 2019 ⁽¹⁾.

2.2 GENERAL SITE DESCRIPTION

The Project Site is located at Siu Ho Wan in North Lantau with an area of about 2 hectares. The layout of the Project Site is illustrated in *Annex A*. The facility received an average of 129 tonnes and treated an average of 116 tonnes of source separated organic waste per day during the reporting month.

2.3 MAJOR ACTIVITIES UNDERTAKEN

A summary of the major activities undertaken in the reporting period is shown in *Table 2.1*.

Table 2.1 Summary of Activities Undertaken in the Reporting Period

| Activities Undertaken in the Reporting Period |
|--|
| <ul style="list-style-type: none"> Systems being operated – waste reception, pre-treatment, CAPCS extraction, the digesters, the centrifuge, the composting tunnels, the desulphurisation, the emergency flare, the CHPs, the ASP and the biological waste water treatment plant (about 129 t/d SSOW received); and Fine tuning of the CHPs and modification of the ASP to control the air emission. |

2.4 PROJECT ORGANISATION AND MANAGEMENT STRUCTURE

The project organisation chart and contact details are shown in *Annex B*.

2.5 STATUS OF ENVIRONMENTAL APPROVAL DOCUMENTS

A summary of the valid permits, licences, and/or notifications on environmental protection for this Project is presented in *Table 2.2*.

Table 2.2 Summary of Environmental Licensing, Notification and Permit Status

| Permit/Licences/ Notification | Reference | Validity Period | Remarks |
|--------------------------------------|------------------------|--|------------------------------------|
| Environmental Permit | FEP-01/395/2010/C | Throughout the Contract | Permit granted on 21 December 2015 |
| Effluent Discharge Licence | WT00038391-2021 | 7 July 2021 – 30 June 2026 | Approved on 7 July 2021 |
| Chemical Waste Producer Registration | WPN 5213-961-O2231-02 | Throughout the implementation of the Project | Approved on 10 November 2017 |
| Waste Disposal Billing Account | Account number: 702310 | Throughout the Contract | - |

(1) As some of the minor items are yet to be closed out in March 2019, the construction phase EM&A programme and Operation Phase EM&A programme were undertaking in parallel in March 2019.

3.1 ENVIRONMENTAL MONITORING

The air quality (including odour) monitoring to be carried out during the commissioning and operation phase of the Project are described below. Although water quality monitoring is not required for the operation phase under the EM&A programme, there are water quality monitoring requirement under the Water Discharge Licence of the plant under the *Water Pollution Control Ordinance* (WPCO). As part of this EM&A programme, the monitoring results will be reviewed to check the compliance with the WPCO requirements.

3.1.1 Air Quality

According to the EM&A Manual and EP requirements, stack monitoring are required during the commissioning and operation phase of the Project.

On-line monitoring (using continuous environmental monitoring system (CEMS) shall be carried out for the centralised air pollution unit (CAPCS), cogeneration units (CHP) and the ammonia stripping plant (ASP) during the commissioning and operation phase. The last calibration was carried out on 15 June 2021.

The monitoring data is transmitted instantaneously to EPD (Regional Office) by telemetry system.

When the on-line monitoring for certain parameter cannot be undertaken, monitoring will be carried out using the following methodology approved by the EPD.

Table 3.1 Sampling and Laboratory Analysis Methodology

| Parameters | Method | Stacks to be Monitored |
|---|------------------|---|
| Gaseous and vaporous organic substances (including methane) | USEPA Method 18 | <ul style="list-style-type: none"> • CAPCS • CHP • ASP |
| Particulate | USEPA Method 5 | <ul style="list-style-type: none"> • CAPCS • CHP • ASP |
| Carbon monoxide (CO) | USEPA Method 10 | <ul style="list-style-type: none"> • CHP • ASP |
| Nitrogen oxides (NO _x) | USEPA Method 7E | <ul style="list-style-type: none"> • CHP • ASP |
| Sulphur dioxide (SO ₂); | USEPA Method 6 | <ul style="list-style-type: none"> • CHP • ASP |
| Hydrogen chloride (HCl) | USEPA Method 26A | <ul style="list-style-type: none"> • CHP • ASP |

| Parameters | Method | Stacks to be Monitored |
|---|------------------|---|
| Hydrogen fluoride (HF) | USEPA Method 26A | <ul style="list-style-type: none"> • CHP • ASP |
| Oxygen (O ₂); | USEPA Method 3A | <ul style="list-style-type: none"> • CAPCS • CHP • ASP |
| Velocity and Volumetric Flow | USEPA Method 2 | <ul style="list-style-type: none"> • CAPCS • CHP • ASP |
| Ammonia (NH ₃) | USEPA CTM 027 | <ul style="list-style-type: none"> • ASP |
| Odour (including NH ₃ and H ₂ S) | EN 13725 | <ul style="list-style-type: none"> • CAPCS |
| Water vapour content (continuous measurement of the water vapour content should not be required if the sample exhaust gas is dried before the emissions are analysed) | USEPA Method 4 | <ul style="list-style-type: none"> • CAPCS • CHP • ASP |
| Temperature | USEPA Method 4 | <ul style="list-style-type: none"> • CAPCS • CHP • ASP |

With reference to the EM&A Manual, the air emission of the stacks shall meet the following emission limits as presented in *Tables 3.2 to 3.5*.

Table 3.2 *Emission Limit for CAPCS Stack*

| Parameter | Emission Level (mg/Nm ³) ^(a) |
|--|---|
| VOCs (including methane) | 680 |
| Dust (or Total Suspended Particulates (TSP)) | 6 |
| Odour (including NH ₃ & H ₂ S) | 220 ^(b) |
| Notes: | |
| (a) Hourly average concentration | |
| (b) The odour unit is OU/Nm ³ | |

Table 3.3 *Emission Limit for CHP Stack*

| Parameter | Maximum Emission Level (mg/Nm ³) ^{(a) (b)} |
|--|---|
| Dust (or Total Suspended Particulates) | 15 |
| Carbon Monoxide | 650 |
| NO _x | 300 |
| SO ₂ | 50 |
| NMVOCs ^(c) | 150 |
| VOCs (including methane) ^(d) | 1,500 |
| HCl | 10 |
| HF | 1 |
| Notes: | |
| (a) All values refer to an oxygen content in the exhaust gas of 6% and dry basis. | |
| (b) Hourly average concentration | |
| (c) NMVOCs should be monitored by gas sampling and laboratory analysis at an agreed interval. For the first 12 months (starting from August 2019), monitoring should be carried out at quarterly intervals. The monitoring frequency should then be reduced to | |

| Parameter | Maximum Emission Level (mg/Nm ³) (a) (b) |
|-----------|--|
| | half-yearly for next 12 months (starting from August 2020). The monitoring of NMVOCs ended in August 2021. |
| | (d) The VOCs emission limit include methane as biogas is adopted as fuel in the combustion process. |

Table 3.4 *Emission Limit for ASP Stack*

| Parameter | Maximum Emission Level (mg/Nm ³) (a) (b) |
|--|--|
| Dust (or Total Suspended Particulates) | 5 |
| Carbon Monoxide | 100 |
| NO _x | 200 |
| SO ₂ | 50 |
| VOCs (including methane) (c) | 20 |
| NH ₃ | 35 |
| HCl | 10 |
| HF | 1 |

Notes:

- (a) All values refer to an oxygen content in the exhaust gas of 11% and dry basis.
- (b) Hourly average concentration
- (c) The VOCs emission limit include methane as biogas is adopted as fuel in the combustion process.

Table 3.5 *Emission Limit for Standby Flaring Gas Unit* ⁽¹⁾

| Parameter | Maximum Emission level (mg/Nm ³) (a) (b) |
|--|--|
| Dust (or Total Suspended Particulates) | 5 |
| Carbon Monoxide | 100 |
| NO _x | 200 |
| SO ₂ | 50 |
| VOCs (including methane) (c) | 20 |
| HCl | 10 |
| HF | 1 |

Notes:

- (a) All values refer to an oxygen content in the exhaust gas of 11% and dry basis.
- (b) Hourly average concentration
- (c) The VOCs emission limit include methane as biogas is adopted as fuel in the combustion process.

3.1.2 Odour

To determine the effectiveness of the proposed odour mitigation measures and to ensure that the operation of the ORRC1 will not cause adverse odour impacts, odour monitoring of the CAPCS stack (see *Section 3.1.1*) and odour patrol will be carried out.

Odour patrol shall be conducted by independent trained personnel/ competent persons in summer months (i.e. from July to September) for the first two operational years of ORRC1 at monthly intervals along an odour

(1) A standby facility. Only operate when the CHPs are not in operation or when the biogas generated exceeded the utilisation rate of the CHPs.

patrol route at the Project Site boundary as shown in *Annex A*⁽¹⁾.

The perceived odour intensity is divided into 5 levels. *Table 3.6* describes the odour intensity for different levels.

Table 3.6 *Odour Intensity Level*

| Level | Odour Intensity |
|-------|--|
| 0 | Not detected. No odour perceived or an odour so weak that it cannot be easily characterised or described |
| 1 | Slight identifiable odour, and slight chance to have odour nuisance |
| 2 | Moderate identifiable odour, and moderate chance to have odour nuisance |
| 3 | Strong identifiable, likely to have odour nuisance |
| 4 | Extreme severe odour, and unacceptable odour level |

Table 3.7 shows the action level and limit level to be used for odour patrol. Should any exceedance of the action and limit levels occurs, actions in accordance with the event and action plan in *Table 3.8* should be carried out.

Table 3.7 *Action and Limit Levels for Odour Nuisance*

| Parameter | Action Level | Limit Level |
|------------------------------------|---|---|
| Odour Nuisance (from odour patrol) | When one documented compliant is received ^(a) , or Odour Intensity of 2 is measured from odour patrol. | Two or more documented complaints are received ^(a) within a week; or Odour intensity of 3 or above is measured from odour patrol. |

Note:

- (a) Once the complaint is received by the Project Proponent (EPD), the Project Proponent would investigate and verify the complaint whether it is related to the potential odour emission from the ORRC1 and its on-site wastewater treatment unit.

Table 3.8 *Event and Action Plan for Odour Monitoring*

| Event | Action | |
|---|--|---|
| | Person-in-charge of Odour Monitoring | Project Proponent ^(a) |
| Action Level | | |
| Exceedance of action level (Odour Patrol) | <ol style="list-style-type: none"> 1. Identify source/reason of exceedance; 2. Repeat odour patrol to confirm finding. | <ol style="list-style-type: none"> 1. Carry out investigation to identify the source/reason of exceedance. Investigation should be completed within 2 weeks; 2. Rectify any unacceptable practice; 3. Implement more mitigation measures if necessary; 4. Inform Drainage Services Department (DSD) or the operator of the Siu Ho Wan Sewage Treatment Works (SHWSTW) if exceedance is considered to be caused by |

(1) The odour patrol route was changed during this reporting period to include sampling points that are frequently visited by visitors and eliminate sampling points that are not visited by visitors.

| Event | Action | |
|---|---|--|
| | Person-in-charge of Odour Monitoring | Project Proponent ^(a) |
| | | the operation of the SHWSTW. 5. Inform North Lantau Refuse Transfer Station (NLTS) operator if exceedance is considered to be caused by the operation of NLTS. |
| Exceedance of action level (Odour Complaints) | 1. Identify source/reason of exceedance; 2. Carry out odour patrol to determinate odour intensity. | 1. Carry out investigation and verify the complaint whether it is related to potential odour emission from the nearby SHWSTW; 2. Carry out investigation to identify the source/reason of exceedance. Investigation should be completed within 2 weeks; 3. Rectify any unacceptable practice; 4. Implement more mitigation measures if necessary; 5. Inform DSD or the operator of the SHWSTW if exceedance is considered to be caused by the operation of the SHWSTW. 6. Inform NLTS operator if exceedance is considered to be caused by the operation of NLTS. |
| Limit Level | | |
| Exceedance of limit level | 1. Identify source/reason of exceedance; 2. Inform EPD; 3. Repeat odour patrol to confirm findings; 4. Increase odour patrol frequency to bi-weekly; 5. Assess effectiveness of remedial action and keep EPD informed of the results; 6. If exceedance stops, cease additional odour patrol. | 1. Carry out investigation to identify the source/reason of exceedance. Investigation should be completed within 2 week; 2. Rectify any unacceptable practice; 3. Formulate remedial actions; 4. Ensure remedial actions properly implemented; 5. If exceedance continues, consider what more/enhanced mitigation measures should be implemented; 6. Inform DSD or the operator of the SHWSTW if exceedance is considered to be caused by the operation of the SHWSTW. |
| Note: | | |
| (a) Project Proponent shall identify an implementation agent. | | |

3.2

SITE AUDIT

Environmental mitigation measures (related to air quality, water quality, waste, land contamination, hazard-to-life, and landscape and visual) to be implemented during the operation phase of the Project are recommended in the approved EIA Report and EM&A Manual and are summarised in *Annex C*. Monthly site audits for operation phase will be carried out to check the implementation of these measures.

3.2.1

Water Quality

Compliance audits are to be undertaken to ensure that a valid discharge licence has been issued by EPD prior to the discharge of effluent from the operation of the Project site. The audit shall be conducted to ensure that the effluent quality is in compliance with the discharge licence requirements. As stipulated in the operation phase discharge licence, effluent discharge are to be sampled monthly from the Effluent Storage Tank, while effluent discharge are to be sampled bi-monthly from the Petrol Interceptors. The effluent quality shall meet the discharge limits as described in *Table 3.9* and *Table 3.10*.

Table 3.9 *Discharge Limits for Effluent from the Effluent Storage Tank*

| Parameters | Discharge Limit (mg/L) |
|--|------------------------|
| Flow Rate (m ³ /day) ^(a) | 645 |
| pH (pH units) ^(b) | 6-10 ^(c) |
| Suspended Solids ^(b) | 800 |
| Biochemical Oxygen Demand (5 days, 20°) ^(b) | 800 |
| Chemical Oxygen Demand ^(b) | 2,000 |
| Oil & Grease ^(b) | 40 |
| Total Nitrogen ^(b) | 200 |
| Total Phosphorus ^(b) | 50 |
| Surfactants (total) ^(b) | 25 |

Notes:

- (a) Flow rate is not a parameter required to be monitored and reported by the Contractor in accordance to Section B2 of the Effluent Discharge Licence under the WPCO.
- (b) Parameters required to be monitored and reported by the Contractor in accordance to Section B2 of the Effluent Discharge Licence under the WPCO.
- (c) Range.

Table 3.10 *Discharge Limits for Effluent from the Petrol Interceptors*

| Parameters | Discharge Limit (mg/L) |
|---------------------------------------|------------------------|
| Flow Rate (m ³ /day) | 245 ^(a) |
| Suspended Solids ^(b) | 30 |
| Chemical Oxygen Demand ^(c) | 80 |
| Oil & Grease ^(c) | 20 |
| Surfactants (total) ^(b) | 15 |

Notes:

- (a) The surface runoff flow rate limit was estimated by the overall yearly rainfall data. As the actual flowrate from the petrol interceptors depends on the weather condition instead of the performance of the petrol interceptor, monitoring and reporting of this parameter is not required. Hence this parameter is not reported in *Table 4.7* and *Table 4.8*.
- (b) Parameter not required to be reported in accordance to Section B2 of the Effluent Discharge Licence under the WPCO.
- (c) Parameters required to be reported in accordance to Section B2 of the Effluent Discharge Licence under the WPCO.

3.2.2

Landscape and Visual

In accordance with EM&A Manual, the landscape and visual mitigation measures shall be implemented.

For operation phase, site inspection shall be conducted once a month for the first year of operation of the Project. All measures as stated in the implementation schedule of the EM&A Manual (see *Annex C*), including compensatory planting, undertaken by both the Contractor and the specialist Landscape Sub-Contractor during the first year of the operation phase shall be audited by a Registered Landscape Architect (RLA) to ensure compliance with the intended aims of the measures and the effectiveness of the mitigation measures. After the one-year maintenance period, the landscape maintenance and monitoring shall be carried out by the Contractor.

4 MONITORING RESULTS

4.1 AIR QUALITY

4.1.1 Commissioning Phase Monitoring

Monitoring results of air quality parameters from stack emissions of the centralised air pollution control system, the ammonia stripping plant and the cogeneration units will be provided once available to show compliance with the monitoring requirements stated in the EM&A Manual (Rev. F) to support the termination of the commissioning phase EM&A programme.

4.1.2 Operation Phase Monitoring

The concentrations of concerned air pollutants emitted from the stacks of the CAPCS, CHP, and ASP during the reporting period are monitored on-line by the continuous environmental monitoring system (CEMS). During the reporting period, there is no need to operate the standby flare and therefore no monitoring of the flare stack was undertaken.

With reference to the emission limits shown in *Tables 3.2, 3.3 and 3.4*, the hourly average concentrations and the number of exceedances of the concerned air emissions monitored for the CAPCS, CHP and ASP during this reporting period are presented in *Tables 4.1 to 4.5*.

It should be noted that measurements recorded under abnormal operating conditions, e.g. start up and stopping of stacks, unstable operation, test runs and interference of sensor, are disregarded.

Table 4.1 *Hourly Average of Parameters Recorded for CAPCS*

| Parameter | Range of Hourly Average Conc. (mg/Nm ³) | Emission Limit (mg/Nm ³) | Exceedance Identified | Remarks |
|---|---|--------------------------------------|-----------------------|---------|
| VOCs (including methane) | 0.00 - 0.00 | 680 | Nil | Nil |
| Dust (or TSP) | 0.00 - 0.00 | 6 | Nil | Nil |
| Odour (including NH ₃ & H ₂ S) ^(a) | 0.00 - 200.29 | 220 | Nil | Nil |

Note:
(a) The odour unit is OU/Nm³.

Table 4.2 *Hourly Average of Parameters Recorded for CHP 1*

| Parameter | Range of Hourly Average Conc. (mg/Nm ³) ^(a) | Max. Emission Limit (mg/Nm ³) | Exceedance Identified | Remarks |
|---|--|---|-----------------------|---------|
| Dust (or TSP) | NA ^(b) | 15 | NA ^(b) | - |
| Carbon Monoxide | NA ^(b) | 650 | NA ^(b) | - |
| NO _x | NA ^(b) | 300 | NA ^(b) | - |
| SO ₂ | NA ^(b) | 50 | NA ^(b) | - |
| VOCs (including methane) ^(c) | NA ^(b) | 1,500 | NA ^(b) | - |
| HCl | NA ^(b) | 10 | NA ^(b) | - |
| HF | NA ^(b) | 1 | NA ^(b) | - |

Notes:

- (a) All values refer to an oxygen content in the exhaust gas of 6% and dry basis.
- (b) CHP 1 was shut down in this reporting period for maintenance and preparation of overhaul
- (c) The VOCs emission limit include methane as biogas is adopted as fuel in the combustion process.

Table 4.3 *Hourly Average of Parameters Recorded for CHP 2*

| Parameter | Range of Hourly Average Conc. (mg/Nm ³) ^(a) | Max. Emission Limit (mg/Nm ³) | Exceedance Identified | Remarks |
|---|--|---|-----------------------|---------|
| Dust (or TSP) | 0 - 3.56 | 15 | Nil | Nil |
| Carbon Monoxide | 0 - 446 | 650 | Nil | Nil |
| NO _x | 0 - 300 | 300 | Nil | Nil |
| SO ₂ | 0 - 42 | 50 | Nil | Nil |
| VOCs (including methane) ^(b) | 0 - 834 | 1,500 | Nil | Nil |
| HCl | 0 - 1.95 | 10 | Nil | Nil |
| HF | 0 - 1 | 1 | Nil | Nil |

Notes:

- (a) All values refer to an oxygen content in the exhaust gas of 6% and dry basis.
- (b) The VOCs emission limit include methane as biogas is adopted as fuel in the combustion process.

Table 4.4 *Hourly Average of Parameters Recorded for CHP 3*

| Parameter | Range of Hourly Average Conc. (mg/Nm ³) ^(a) | Max. Emission Limit (mg/Nm ³) | Exceedances Identified | Remarks |
|---|--|---|---------------------------|----------------------------------|
| Dust (or TSP) | 0 - 14 | 15 | Nil | Nil |
| Carbon Monoxide | 0 - 593 | 650 | Nil | Nil |
| NO _x | 0 - 287 | 300 | Nil | Nil |
| SO ₂ | 0 - 53 | 50 | Identified ^(d) | De-sulphurisation system tripped |
| VOCs (including methane) ^(b) | 0 - 1,151 | 1,500 | Nil | Nil |
| HCl | 0 - 6 | 10 | Nil | Nil |

| Parameter | Range of Hourly Average Conc. (mg/Nm ³) ^(a) | Max. Emission Limit (mg/Nm ³) | Exceedances Identified | Remarks |
|-----------|--|---|------------------------|---------|
| HF | 0 - 1 | 1 | Nil | Nil |

Notes:

(a) All values refer to an oxygen content in the exhaust gas of 6% and dry basis.

(b) The VOCs emission limit include methane as biogas is adopted as fuel in the combustion process.

(c) Date with exceedances on SO₂ (number of exceedance on the day) was identified on 19 (2) December 2021.

Table 4.5 *Hourly Average of Parameters Recorded for ASP*

| Parameter | Range of Hourly Average Conc. (mg/Nm ³) ^(a) | Max. Emission Limit (mg/Nm ³) | Exceedances Identified | Remarks |
|---|--|---|---------------------------|---------------------------------------|
| Dust (or TSP) | 0 - 3.73 | 5 | Nil | Nil |
| Carbon Monoxide | 0 - 9 | 100 | Nil | Nil |
| NO _x | 0 - 401.47 | 200 | Identified ^(c) | System unstable (unstable water flow) |
| SO ₂ | 0 - 76 | 50 | Identified ^(d) | De-sulphurisation system tripped |
| VOCs (including methane) ^(b) | 0 - 35 | 20 | Identified ^(e) | System unstable (unstable water flow) |
| NH ₃ | 0 - 268 | 35 | Identified ^(f) | System unstable (unstable water flow) |
| HCl | 0 - 0.14 | 10 | Nil | Nil |
| HF | 0 - 1 | 1 | Nil | Nil |

Notes:

(a) All values refer to an oxygen content in the exhaust gas of 11% and dry basis.

(b) The VOCs emission limit include methane as biogas is adopted as fuel in the combustion process.

(c) Dates with exceedances on NO_x (number of exceedances on the day) were identified on 1 (1), 2 (2), 6 (1), 7 (2), 8 (8), 9 (9), 14 (14), 15 (12), 16 (3), 21 (3), 23 (2), 24 (7), 25 (1), 27 (6), 28 (1), 29 (4) and 31 (1) December 2021.

(d) Dates with exceedances on SO₂ (number of exceedances on the day) were identified on 24 (6), 25 (2) and 29 (4) December 2021

(e) Date with exceedances on VOCs (number of exceedances on the day) was identified on 1 (1) December 2021.

(f) Dates with exceedances on NH₃ (number of exceedances on the day) were identified on 3 (2), 4 (2), 10 (1), 11 (1), 12 (1), 15 (1), 17 (1), 19 (3), 20 (5), 21 (2), 23 (5), 24 (1), 25 (1) and 31 (3) December 2021.

4.2 ODOUR

4.2.1 Operation Phase Monitoring

No odour patrol was required to be conducted for this reporting period.

4.3

WATER QUALITY

4.3.1

Operation Phase Monitoring

Effluent discharge was sampled from the Effluent Storage Tank monthly and from the Petrol Interceptor(s) bi-monthly as stipulated in the operation phase discharge licence. The results of the discharge samples from the Effluent Storage Tank are recorded in *Table 4.6* and the results from the Petrol Interceptors are recorded in *Table 4.7* and *Table 4.8*.

Table 4.6 *Results of the Discharge Sample from the Effluent Storage Tank*

| Parameters | Discharged Effluent Concentration (mg/L) | Discharge Limit (mg/L) | Compliance with Discharge Limit |
|--|--|------------------------|---------------------------------|
| Flow Rate (m ³ /day) ^(a) | 50 – 268 | 645 | Yes |
| pH (pH units) ^{(b) (d)} | 7.94 – 8.28 | 6-10 ^(c) | Yes |
| Suspended Solids ^{(b) (d)} | 196 | 800 | Yes |
| Biochemical Oxygen Demand (5 days, 20°) ^{(b) (d)} | 72 | 800 | Yes |
| Chemical Oxygen Demand ^{(b) (d)} | 1,110 | 2,000 | Yes |
| Oil & Grease ^{(b) (d)} | <5 | 40 | Yes |
| Total Nitrogen ^{(b) (d)} | 83.6 | 200 | Yes |
| Total Phosphorus ^{(b) (d)} | 22.8 | 50 | Yes |
| Surfactants (total) ^{(b) (d)} | 1.2 | 25 | Yes |

Notes:

- (a) Parameter not required to be reported in accordance to Section B2 of the Effluent Discharge Licence under the WPCO.
- (b) Parameters required to be reported in accordance to Section B2 of the Effluent Discharge Licence under the WPCO.
- (c) Daily Average.
- (d) Effluent sample collected on 20 December 2021.

Table 4.7 *Results of the Discharge Sample from the Petrol Interceptor 1*

| Parameters | Discharged Effluent Concentration (mg/L) | Discharge Limit (mg/L) | Compliance with Discharge Limit |
|---------------------------------------|--|------------------------|---------------------------------|
| Suspended Solids ^(b) | 9 ^(a) | 30 | Yes |
| Chemical Oxygen Demand ^(c) | 41 ^(a) | 80 | Yes |
| Oil & Grease ^(c) | <5 ^(a) | 20 | Yes |
| Surfactants (total) ^(b) | <1.0 ^(a) | 15 | Yes |

Notes:

- (a) Sampling was carried out on 9 Dec 2021.
- (b) Parameter not required to be reported in accordance to Section B2 of the Effluent Discharge Licence under the WPCO.
- (c) Parameters required to be reported in accordance to Section B2 of the Effluent Discharge Licence under the WPCO.

Table 4.8 Results of the Discharge Sample from the Petrol Interceptor 2

| Parameters | Discharged Effluent Concentration (mg/L) | Discharge Limit (mg/L) | Compliance with Discharge Limit |
|---------------------------------------|--|------------------------|---------------------------------|
| Suspended Solids ^(b) | 34 ^(a) | 30 | No |
| Chemical Oxygen Demand ^(c) | 167 ^(a) | 80 | No |
| Oil & Grease ^(c) | 6 ^(a) | 20 | Yes |
| Surfactants (total) ^(b) | <1.0 ^(a) | 15 | Yes |

Notes:

- (a) Sampling was carried out on 9 Dec 2021.
- (b) Parameter not required to be reported in accordance to Section B2 of the Effluent Discharge Licence under the WPCO.
- (c) Parameters required to be reported in accordance to Section B2 of the Effluent Discharge Licence under the WPCO.

4.4 WASTE MANAGEMENT

4.4.1 Operation Phase Monitoring

Wastes generated from the operation of the Project include chemical waste, wastes generated from pre-treatment process and general refuse ⁽¹⁾. Reference has been made to the Monthly Summary Waste Flow Table prepared by the Contractor (see *Annex D*). With reference to the relevant handling records and trip tickets of this Project, the quantities of different types of waste generated from the operation of the Project in the reporting month are summarised in *Table 4.9*.

Table 4.9 Quantities of Waste Generated from the Operation of the Project

| Month / Year | Chemical Waste Disposal of at CWTC | Waste Generated from Pre-treatment Process | | General Refuse | |
|---------------|------------------------------------|--|-------------------------|--|-------------------------|
| | | Disposed of at Landfill ^(a) | Recycled ^(b) | Disposed of at Landfill ^(a) | Recycled ^(c) |
| December 2021 | 0 L ^(d) | 392.44 tonnes | 0.67 tonnes | 2.53 tonnes ^(e) | 0.00 tonne |

Notes:

- (a) Waste generated from pre-treatment process and general refuse other than chemical waste and recyclables were disposed of at NENT Landfill by sub-contractors.
- (b) Among waste generated from pre-treatment process, 0.00 tonne of metals, 0.67 tonnes of papers/ cardboard packing and 0.00 tonne of plastics were sent to recyclers for recycling during the reporting period.
- (c) Among general refuse, 0.00 kg of metals, 0.00 kg of papers/ cardboard packing and 0.00 kg of plastics were sent to recyclers for recycling during the reporting period.
- (d) No chemical waste was generated in December 2021.
- (e) It was assumed that four 240-litre bins filled with 80% of general refuse were collected at each collection. The general refuse density was assumed to be around 0.15 kg/L.

(1) Public fill and construction waste may only be generated during maintenance works when there are civil or structural works.

5 *SITE AUDIT*

5.1 *ENVIRONMENTAL SITE AUDIT*

5.1.1 *Operation Phase*

The monthly inspection for the operation phase of the Project on 10 December 2021 covered the operation phase environmental site audit. Joint site inspection was conducted by representatives of the Contractor, IEC, and the MT on 10 December 2021 as required for the operation of the Project.

The audits checked the implementation of the recommended mitigation measures for air quality, landscape and visual, water quality, waste (land contamination) and hazard-to-life stated in the Implementation Schedule (see *Annex C*).

Key observations during the reporting period are summarised as follows:

10 December 2021

- No particular observation during this inspection.

Other than the above observations, the Contractor has implemented environmental mitigation measures recommended in the approved EIA Report and EM&A Manual.

5.2 *LANDSCAPE AND VISUAL AUDIT*

Inspection of the landscape and visual mitigation measures for the operation phase of the Project was performed on 10 December 2021.

It was confirmed that the necessary landscape and visual mitigation measures during the operation phase as summarised in *Annex C* were generally implemented by the Contractor. No specific observation was found during the joint site inspection on 10 December 2021. No non-compliance in relation to the landscape and visual mitigation measures was identified during the site audits in this reporting period and therefore no further actions are required. The ET/MT will keep track of the EM&A programme to check compliance with environmental requirements and the proper implementation of all necessary mitigation measures.

6.1 SUMMARY OF ENVIRONMENTAL NON-COMPLIANCE AND DEFICIENCIES

Non-compliance of emission limits of SO₂ from CHP and NO_x, SO₂, VOCs and NH₃ from ASP were recorded during the reporting period.

The Contractor has reviewed the organic waste treatment processes (i.e. waste reception, waste pre-treatment, anaerobic digesters, and composting processes) and found that they were operated normally during the reporting period. The Contractor has investigated the air pollution control system and the combustion system of the ASP and the de-sulphurisation systems, the potential causes for the exceedance were identified.

The exceedances of NO_x, VOCs and NH₃ from ASP occurred due to system instability caused by blockage of the stripping column. To ensure stripping efficiency and stable operation of the ASP, the Contractor has arranged acid-clearing of the blockage in January 2022 and the cleaning of the packaging in the future. The exceedance of SO₂ from the de-sulphurisation system of ASP and CHP was caused by blockage of the hot water system, which was unblocked as soon as the issue was identified.

Non-compliance of discharge limit of Suspended Solids and Chemical Oxygen Demand from Petrol Interceptor 2 was recorded during the reporting period. The Contractor suspected that the exceedance resulted from the washing down of food waste residue from the ad-hoc unloading and unpacking of food waste near the sampling point between mid-November 2021 and early December 2021. The Contractor has scheduled cleaning of the Petrol Interceptor in January 2022 and will schedule routine cleaning after future ad-hoc pre-processing work on site.

The investigation reports of the above exceedance are presented in *Annex F*.

6.2 SUMMARY OF ENVIRONMENTAL COMPLAINT

No complaint was received during the reporting period.

6.3 SUMMARY OF ENVIRONMENTAL SUMMON AND SUCCESSFUL PROSECUTION

No summon/prosecution was received during the reporting period. The cumulative summons/prosecution log is shown in *Annex E*.

7 *FUTURE KEY ISSUES*

7.1 *KEY ISSUES FOR THE COMING MONTH*

Activities to be undertaken for the coming reporting period are:

- Operation of the Project.
- Fine tuning of the CHPs and modification of the ASP to control the air emission.

This EM&A Report presents the EM&A programme undertaken during the reporting period from **1 to 30 November 2021** in accordance with EM&A Manual (Version F) and requirements of EP (FEP-01/395/2010/C).

For the operation phase, exceedances of the emission limits for the ASP stack monitoring and the exceedance of the discharge limit from Petrol Interceptor 2 were recorded under normal operating conditions during the reporting period (see *Table 8.1* and *Table 8.2*).

Table 8.1 *Exceedances for Stack Emissions*

| Stack | Exceedances During the Reporting Period |
|-------------------------------|--|
| Cogeneration Units 3 (CHP 3) | <ul style="list-style-type: none"> Exceeded emission limit of SO₂ on 19 December 2021. |
| Ammonia Stripping Plant (ASP) | <ul style="list-style-type: none"> Exceeded emission limit of NO_x on 1, 2, 6, 7, 8, 9, 14, 15, 16, 21, 23, 24, 25, 27, 28, 29 and 31 December 2021. Exceeded emission limit of SO₂ on 14, 15 and 29 December 2021. Exceeded emission limit of VOCs on 1 December 2021. Exceeded emission limit of NH₃ on 3, 4, 10, 11, 12, 15, 17, 19, 20, 21, 23, 24, 25 and 31 December 2021. |

Non-compliance of emission limits from the CHP and ASP was recorded during this reporting period. The exceedances of NO_x, VOCs and NH₃ from ASP occurred due to system instability caused by blockage of the stripping column. To ensure stripping efficiency and stable operation of the ASP, the Contractor has arranged acid-clearing of the blockage in January 2022 and the cleaning of the packaging in the future. The exceedances of SO₂ from the desulphurisation system for CHP and ASP were caused by blockage of the hot water system, which was unblocked as soon as the issue was identified.

Table 8.2 *Exceedances for Petrol Interceptor 2*

| Effluent Discharge Point | Exceedances During the Reporting Period |
|--------------------------|--|
| Petrol Interceptor 2 | <ul style="list-style-type: none"> Exceeded emission limit of Suspended Solid 9 December 2021. Exceeded emission limit of Chemical Oxygen Demand on 9 December 2021. |

Non-compliance of discharge limit of Suspended Solids and Chemical Oxygen Demand from Petrol Interceptor 2 was recorded during the reporting period. The Contractor suspected that the exceedance resulted from the washing down of food waste residue from the ad-hoc unloading and unpacking of food waste near the sampling point between mid-November 2021 and early December 2021. The Contractor has scheduled cleaning of the Petrol Interceptor in January 2022 and will schedule routine cleaning after future ad-hoc pre-processing work on site.


The environmental control /mitigation measures related to air quality, water quality, waste (including land contamination prevention), hazard-to-life and landscape and visual recommended in the approved EIA Report and the EM&A Manual were properly implemented by the Contractor during the reporting month.

Monthly landscape and visual monitoring were conducted in the reporting period. The necessary landscape and visual mitigation measures recommended in the approved EIA Report were generally implemented by the Contractor.

No complaint/summon/prosecution was received.

Annex A

Project Layout



Key
 Patrol Route

| | | | | |
|-----|----------|----|-----|----------------------------|
| A01 | 05/03/15 | CW | MB | IMTECH BACKGROUNDS UPDATED |
| A00 | 18/02/15 | CW | MB | DRAFT ISSUE |
| REV | DATE | BY | APP | DESCRIPTION |

CLIENT
 ENVIRONMENTAL PROTECTION DEPARTMENT
 GOVERNMENT OF THE HKSAR

CLIENT'S CONSULTANT
 **AECOM**
 AECOM ASIA CO. LTD.

CONTRACTOR
  
 OSCAR BIOENERGY JV

LEAD DESIGNER
 **ARUP**
 Ove Arup & Partners Hong Kong Limited

ENVIRONMENTAL TEAM
 **ERM**
 ERM HONG KONG LIMITED

INDEPENDENT CONSULTANTS
 **MEINHARDT**
 Meinhardt Infrastructure and Environment Limited
 邁達基建築環保工程顧問有限公司

PROJECT
 ORGANIC WASTE TREATMENT FACILITIES
 PHASE 1
 EP/SP/61/10

STATUS
 DRAFT ISSUE

DRAWING TITLE
 SITE LAYOUT


| | | |
|----------------------------|---------------------------------|-------------|
| DRAWN CW | CHECKED RS | APPROVED DP |
| SCALE 1:500@A1 / 1:1000@A3 | DATE 12/02/15 | |
| JOB NO. 239956 | DRAWING NO. DR-OAP-20-0-CA-1001 | REV. A01 |

Plot Time: 05/03/15 21:20:07
 Plot Location: C:\Users\mathew.brown\Documents\QWTF_Architectural Working Model (Combined) CEH_mathew.brown.rvt

Annex B

Project Organisation Chart with Contact Details

Project Organization (with contact details)



Annex C

Implementation Schedule of Mitigation Measures

Annex C Summary of Mitigation Measures Implementation Schedule for Operation Phase

| EIA Ref. | EM&A Log Ref. | Environmental Protection Measures | Location/ Timing | Status |
|--|-------------------|---|---|--------|
| <i>Summary of Environmental Mitigation Measures in the EIA and EM&A Manual</i> | | | | |
| <i>A. Air Quality</i> | | | | |
| 3.78 | 2.7 & 2.13 – 2.19 | <u>Air Pollution Control (Construction Dust) Regulation & Good Site Practices</u> <ul style="list-style-type: none"> •Commissioning tests shall be conducted to confirm the centralized air pollution control unit, the cogen units, the standby flaring unit and ASP against the design emission levels as stated in Tables 2.2 - 2.5. •Odour monitoring shall be conducted at the stack exhaust of the centralized air pollution control unit weekly in the first month of the commissioning stage. | OWTF Stacks/ During Commissioning Stage | √ |
| 3.78 | 2.7-2.12 | <u>Air Pollution Control and Stack Monitoring</u> <ul style="list-style-type: none"> •Stack monitoring shall be installed for the centralized air pollution control unit, cogen units and ASP of OWTF to ensure that the air emissions from OWTF would meet the design emission limits as well as EPD criteria. | During Operation | √ |
| 3.78 | 2.20- 2.28 | •Odour Patrol at site boundary of OWTF | OWTF Site Boundary/ During Operation (The need to continue the odour patrol after the end of the 2-year monitoring period would depend on the monitoring results and should be agreed with EPD) | N/A |
| <i>B. Hazard to Life</i> | | | | |
| 4.103 | 3.4 | <u>Operation Phase</u> <ul style="list-style-type: none"> •3m high fence should be constructed along the boundary facing the SHWWTW •Emergency evacuation procedures should be formulated and the Contractor should ensure on site staff should be familiar with these procedures. Diagram showing the escape routes to a safe place should be posted in the site notice boards and at the entrance/exit of site. A copy of the latest version emergency procedures should be dispatched to Tung Chung Fire Station for reference once available. •The emergency procedures should specify means of providing a rapid and direct warning (e.g. Siren and Flashing Light) to personnel on site in the event of chlorine gas release in the SHWWTW. | Work Site / During Operation Period | √ |

| EIA Ref. | EM&A Log Ref. | Environmental Protection Measures | Location/ Timing | Status |
|-------------------------|---------------|---|--|--------|
| | | <ul style="list-style-type: none"> •The Contractor should establish a communication channel with the SHWWTW operation personnel and FSD. In case of any hazardous incidents in the treatment works, operation personnel of SHWWTW should advise the Contractor to inform personnel on site to proceed with emergency procedure. The Contractor should appoint a Liaison Officer to communicate with FSD Incident Commander on site in case of emergency. •Periodic drills should be coordinated and conducted to ensure all on site personnel are familiar with the emergency procedures. Upon completion of the drills, a review on every step taken should be conducted to identify area of improvement. Prior notice of periodic drills should be given to Station Commander of Tung Chung Fire Station. Joint operational exercise with FSD and SHWWTW is recommended. | | |
| <i>C. Water Quality</i> | | | | |
| 5.44 | 4.5 | <p><u>Wastewater from Organic Waste Treatment Process</u></p> <p>The Project site will be equipped with an adequately sized wastewater treatment plant. A high rate type of active sludge system specifically designed for the removal of nitrogen components from the wastewater in combination with conversion of residual BOD and COD would be deployed. The wastewater treatment plant would also be incorporated with SHARON or annamox technology or equivalent to achieve high total overall nitrogen removal. Wastewater generated from the OWTF (including wastewater from dewatering process, leachate from waste reception area, condensate from biogas handling, wastewater from scrubber of air treatment system and any surplus water from truck washing facility) will be diverted to the wastewater treatment plant. Treated effluent will then be stored temporarily in order to be used as process water within the plants. The storage volume would be around 20 m³. Overflow from the tank will be discharged to foul sewers. The polluting parameters in effluent shall be in compliance with the requirements specified in the TM- DSS. The design, installation and operation of the wastewater treatment plant shall be licensed under the Waste Disposal Ordinance and subject to the effluent monitoring as required under the WPCO which is under the ambit of regional office (RO) of EPD. To ensure that wastewater can be adequately treated and effluent from treatment plant can meet the standards listed in TM- DSS, the following mitigation measure should be conducted.</p> <ul style="list-style-type: none"> • Cleaning and maintenance of treatment facilities should be conducted on a regular basis to ensure that removal rate of each treatment facility would not be reduced. • Cleaning and maintenance of pipelines should be carried out on a regular basis to prevent block of pipeline and leaching of wastewater, and therefore prevent overflowed or leached wastewater discharging into nearby drainages and water streams. • Regular site inspection should be conducted to ensure that no wastewater can be directly discharged into nearby water streams. | Work Site / During Design & Operation Period | √ |

| EIA Ref. | EM&A Log Ref. | Environmental Protection Measures | Location/ Timing | Status |
|----------------------------|---------------|--|--|--------|
| 5.55 | 4.5 | In the scrubber, spraying water should be re-circulated to minimize the need for external water. The spraying water would be collected at the bottom of the scrubber. Excess water would be discharged to the wastewater treatment plant as described in Section 5.54. | Work Site / During Design & Operation Period | √ |
| 5.56 | 4.5 | The waste reception, treatment facilities and compost storages of OWTF should be located in enclosed buildings to prevent generation of contaminated rain runoff. All surface runoff such as washed water generated in the treatment processes areas should be properly collected and diverted to the on-site wastewater treatment plant as described in Section 5.54. | Work Site / During Design & Operation Period | √ |
| 5.57 | 4.5 | All drainage system for collection and transferring wastewater generated in the OWTF to the on-site wastewater treatment plant as described in Section 5.54 should be capable of preventing clogging and easy maintenance and cleaning. | Work Site / During Design & Operation Period | √ |
| <i>D. Waste Management</i> | | | | |
| 6.50 | 5.12 | <p><u>Good Site Practices</u></p> <p>Good operational practices should be adopted to Minimize waste management impacts:</p> <ul style="list-style-type: none"> •Obtain the necessary waste disposal permits from the appropriate authorities, in accordance with the Waste Disposal Ordinance (Cap. 354), Waste Disposal (Chemical Waste) (General) Regulation and the Land (Miscellaneous Provision) Ordinance (Cap. 28); •Nomination of an approved person to be responsible for good site practice, arrangements for collection and effective disposal to an appropriate facility of all wastes generated at the site; •Use of a waste haulier licensed to collect specific category of waste; •A trip-ticket system should be included as one of the contractual requirements and implemented by the Environmental Team to monitor the disposal of solid wastes at public filling facilities and landfills, and to control fly tipping. Reference should be made to ETWB TCW No. 31/2004. •Training of site personnel in proper waste management and chemical waste handling procedures; •Separation of chemical wastes for special handling and appropriate treatment at a licensed facility; •Routine cleaning and maintenance programme for drainage systems, sumps and oil interceptors; •Provision of sufficient waste disposal points and regular collection for disposal; •Adoption of appropriate measures to minimize windblown litter and dust during transportation of waste, such as covering trucks or transporting wastes in enclosed containers; and •Implementation of a recording system for the amount of wastes generated, recycled and | During Operation Period | √ |

| EIA Ref. | EM&A Log Ref. | Environmental Protection Measures | Location/ Timing | Status |
|-----------|---------------|---|--|--------|
| | | disposed of (including the disposal sites). | | |
| 6.51 | 5.13 | <p><u>Waste Reduction Measures</u></p> <p>Good management and control can prevent the generation of significant amounts of waste. It is recommended that the following good operational practices should be adopted to ensure waste reduction:</p> <ul style="list-style-type: none"> •Segregation and storage of different types of waste in different containers, skips or stockpiles to enhance reuse or recycling of materials and their proper disposal; •Encourage collection of aluminum cans, plastic bottles and packaging material (e.g. carton boxes) and office paper by individual collectors. Separate labelled bins should be provided to help segregate this waste from other general refuse generated by the work force; and •Any unused chemicals or those with remaining functional capacity should be reused as far as practicable. | During Operation Period | √ |
| 6.52 | 5.14 | <p><u>Wastes Generated from Pre-Treatment Process</u></p> <p>Wastes generated from pre-treatment process should be recycled as far as possible. Wastes generated from pre-treatment process should also be separated from any chemical waste and stored in covered skips. The recyclables should be collected by licensed collectors, while the rest of the waste should be removed from the site on a daily basis to minimize odour, pest and litter impacts. Open burning must be strictly prohibited.</p> | Pre-Treatment Process/ During Operation Period | √ |
| 6.53-6.56 | 5.15-5.18 | <p><u>Chemical Wastes</u></p> <ul style="list-style-type: none"> •Chemical waste generated from machinery maintenance and servicing should be managed in accordance with Code of Practice on the Packaging, Labelling and storage of Chemical Wastes under the provisions of Waste Disposal (Chemical Waste) (General) Regulation. The chemical waste should be collected by drum-type containers and removed by licensed chemical waste contractors. •Plant / equipment maintenance schedules should be planned in order to minimize the generation of chemical waste. •Non-recyclable chemical wastes and lubricants should be disposed of at appropriate facilities, such as CWTC. Copies or counterfoils from collection receipts issued by the licensed waste collector should be kept for recording purpose. •Recyclable chemical waste will be transported off-site for treatment by a licensed collector. The Contractor will need to register with EPD as a chemical waste producer. Where possible, chemical wastes (e.g. waste lubricants) would be recycled at appropriate facilities, such as Dunwell's oil re-refinery. | Whole Site / During Operation Period | √ |
| 6.57-6.58 | 5.19-5.20 | <u>General Refuse</u> | Whole Site / During Operation | √ |

| EIA Ref. | EM&A Log Ref. | Environmental Protection Measures | Location/ Timing | Status |
|---|---------------|--|--|--------|
| | | <ul style="list-style-type: none"> Waste generated in offices should be reduced through segregation and collection of recyclables. To promote the recycling of wastes such as used paper, aluminum cans and plastic bottles, it is recommended that recycling bins should be clearly labelled and placed at locations with easy access. For the collection of recyclable materials, they should be collected by licensed collectors. General refuse, other than segregated recyclable wastes, should be separated from any chemical waste and stored in covered skips. The general refuse should be removed from the site on a daily basis to minimize odour, pest and litter impacts. Also, open burning of refuse must be strictly prohibited. | Period | |
| <i>E. Proposed Land Contamination Preventive Measures</i> | | | | |
| 6.65 | 5.21 (i) | <u>Fuel Oil Containers</u> <ul style="list-style-type: none"> Fuel oil should be stored in suitable containers. All fuel oil containers should be securely closed. Appropriate labels showing the name of fuel oil should be posted on the containers. Drip trays should be provided for all containers. | Fuel Oil Storage Containers /During Operation Period | √ |
| 6.65 | 5.21 (ii) | <u>Storage Area</u> <ul style="list-style-type: none"> Distance between the fuel oil refuelling points and the fuel oil containers should be minimized. The storage area should be used for fuel oil storage only. No surface water drains or foul sewers should be connected to the storage area. The storage area should be enclosed by three sides by a wall and have an impermeable floor or surface. | Fuel Oil Storage Area /During Operation Period | √ |
| 6.65 | 5.21 (iii) | <u>Fuel Oil Spillage Response</u> An Oil Spill Response Plan should be prepared by the operator to document the appropriate response procedures for oil spillage incident in detail. General procedures to be taken in case of fuel oil spillage are presented below. <ul style="list-style-type: none"> <u>Training</u> Training on oil spill response actions should be given to relevant staff. The training should cover the followings: <ul style="list-style-type: none"> Tools & resources to combat oil spillage and fire, e.g. locations of oil spill handling equipment and firefighting equipment; General methods to deal with oil spillage and fire incidents; Procedures for emergency drills in the event of oil spills and fire; and Regular drills should be carried out. <u>Communication</u> Establish communication channel with the Fire Services Department (FSD) and EPD to | Whole Site / During Operation Phase | √ |

| EIA Ref. | EM&A Log Ref. | Environmental Protection Measures | Location/ Timing | Status |
|----------|---------------|--|--------------------------------------|--------|
| | | <p>report any oil spillage incident so that necessary assistance from relevant department could be quickly sought.</p> <ul style="list-style-type: none"> • <u>Response Procedure</u> Any fuel oil spillage within the Project Site should be immediately reported to the Site Manager with necessary details including location, source, possible cause and extent of the spillage Site Manager should immediately attend to the spillage and initiate any appropriate action to confine and clean up the spillage. The response procedures should include the following: <ul style="list-style-type: none"> - Identify and isolate the source of spillage as soon as possible. - Contain the oil spillage and avoid infiltration into soil / groundwater and discharge to storm water channels. - Remove the oil spillage. - Clean up the contaminated area. - If the oil spillage occurs during refuelling, the refuelling operation should immediately be stopped. - Recovered contaminated fuel oil and the associated material to remove the spilled oil should be considered as chemical waste. The handling and disposal procedures for chemical wastes are discussed in the following paragraphs. | | |
| 6.66 | 5.22 (i) | <p><u>Chemicals and Chemical Wastes Handling & Storage</u></p> <ul style="list-style-type: none"> • Chemicals and chemical wastes should only be stored in suitable containers in purpose-built areas. • The storage of chemical wastes should comply with the requirements of the Code of Practice on the Packaging, Labelling and Storage of Chemical Wastes. • The storage areas for chemicals and chemical wastes should have an impermeable floor or surface. The impermeable floor I surface should possess the following properties: <ul style="list-style-type: none"> - Not liable to chemically react with the materials and their containers to be stored. - Able to withstand normal loading and physical damage caused by container handling - The integrity and condition of the impermeable floor or surface should be inspected at regular intervals to ensure that it is satisfactorily maintained • For liquid chemicals and chemical wastes storage, the storage area should be bonded to contain at least 110% of the storage capacity of the largest containers or 20% of the total quantity of the chemicals/chemical wastes stored, whichever is the greater. | Whole Site / During Operation Period | √ |

| EIA Ref. | EM&A Log Ref. | Environmental Protection Measures | Location/ Timing | Status |
|-------------|---------------|---|--------------------------------------|--------|
| | | <ul style="list-style-type: none"> Storage container should be checked at regular intervals for their structural integrity and to ensure that the caps or fill points are tightly closed. Chemical handling should be conducted by trained workers under supervision. | | |
| 6.66 | 5.22 (ii) | <p><u>Chemicals and Chemical Wastes Spillage Response</u> A Chemicals and / or Chemical Wastes Spillage Response Plan should be prepared by the operator to document in detail the appropriate response procedures for chemicals or chemical wastes spillage incidents. General procedures to be undertaken in case of chemicals I chemical waste spillages are presented below</p> <ul style="list-style-type: none"> Training Training on spill response actions should be given to relevant staff. The training should cover the followings: <ul style="list-style-type: none"> Tools & resources to handle spillage, e.g. locations of spill handling equipment; General methods to deal with spillage; and Procedures for emergency drills in the event of spills. Communication Establish communication channel with Fire Services Department (FSD) and EPD to report the spillage incident so that necessary assistance from relevant department could be quickly sought. Response Procedures Any spillage within OWTF site should be reported to the Site Manager. Site Manager shall attend to the spillage and initiate any appropriate actions needed to confine and clean up the spillage. The response procedures should include the followings: <ul style="list-style-type: none"> Identify and isolate the source of spillage as soon as possible; Contain the spillage and avoid infiltration into soil / groundwater and discharge to storm water channels (in case the spillage occurs at locations out of the designated storage areas); Remove the spillage; the removal method / procedures documented in the Material Safety Data Sheet (MSDS) of the chemicals spilled should be observed; Clean up the contaminated area (in case the spillage occurs at locations out of the designated storage areas); and The waste arising from the cleanup operation should be considered as chemical wastes. | Whole Site / During Operation Period | √ |
| 6.67 - 6.69 | 5.23- 5.25 | <p><u>Incident Record</u></p> <ul style="list-style-type: none"> After any spillage, an incident report should be prepared by the Site Manager. The incident report should contain details of the incident including the cause of the | Whole Site / During Operation Period | √ |

| EIA Ref. | EM&A Log Ref. | Environmental Protection Measures | Location/ Timing | Status |
|--------------------------------|---------------|---|--|--------|
| | | <p>incident, the material spilled and estimated spillage amount, and also the response actions undertaken. The incident record should be kept carefully and able to be retrieved when necessary.</p> <ul style="list-style-type: none"> • The incident report should provide sufficient details for the evaluation of any environmental impacts due to the spillage and assessment of the effectiveness of measures taken. • In case any spillage or accidents results in significant land contamination, EPD should be informed immediately and the Project operator should be responsible for the cleanup of the affected area. The responses procedures described in Sections 6.65 - 6.66 of the EIA Report should be followed accordingly together with the land contamination assessment and remediation guidelines stipulated in the <i>Guidance Manual for Use of Risk-based Remediation Goals for Contaminated Land Management</i> and the <i>Guidance Note for Contaminated Land Assessment and Remediation</i>. | | |
| <i>F. Landscape and Visual</i> | | | | |
| 7.98 & Table 7.8 | Table 6.2 | <p><u>Operation Phase</u></p> <ul style="list-style-type: none"> • Aesthetic design of the facade, including its colour theme, pattern, texture, materials, finishing and associated structures to harmonize with the surrounding settings • Grass / groundcover planting to soften the roof • Heavy standard tree planting to screen proposed associated structures • Grasscrete paving to soften the harshness of large paved surface areas wherever possible | Within Project Area / During Design & Operation Stages | √ |

Remark:

- √ Compliance of Mitigation Measures
- <> Compliance of Mitigation but need improvement
- x Non-compliance of Mitigation Measures
- ▲ Non-compliance of Mitigation Measures but rectified by OSCAR Bioenergy JV
- Δ Deficiency of Mitigation Measures but rectified by OSCAR Bioenergy JV
- N/A Not Applicable in Reporting Period

Annex D

Waste Flow Table

No. EP/SP/61/10 of Organic Resources Recovery Centre (Phase 1)
Monthly Summary Waste Flow Table

| Month | Chemical Waste | Waste Generated from Pretreatment Process | | | | General Refuse | | | | | | | |
|----------------|----------------|---|---------------------|---|-----------------------|--|-------|---------------------|-------|---|-------|-----------------------|-------|
| | | Disposed of at Landfill (see Note 1) | Metals (see Note 2) | Paper/ cardboard packaging (see Note 2) | Plastics (see Note 3) | Disposed of at Landfill (see Note 1 & 4) | | Metals (see Note 2) | | Paper/ cardboard packaging (see Note 2) | | Plastics (see Note 3) | |
| | Litre | tonne | tonne | tonne | tonne | No. of collection | tonne | No. of collection | tonne | No. of collection | tonne | No. of collection | tonne |
| March 2019 | 1,200 | 477.08 | 0 | 0 | 0 | 26 | 1.50 | 0 | 0 | 0 | 0 | 0 | 0 |
| April 2019 | 0 | 455.60 | 0 | 0 | 0 | 22 | 1.27 | 0 | 0 | 0 | 0 | 0 | 0 |
| May 2019 | 1,000 | 528.22 | 0 | 0 | 0 | 25 | 2.88 | 0 | 0 | 0 | 0 | 1 | 0.39 |
| June 2019 | 0 | 459.23 | 0 | 0 | 0 | 24 | 2.76 | 0 | 0 | 0 | 0 | 0 | 0 |
| July 2019 | 0 | 521.79 | 0 | 0 | 0 | 26 | 3.00 | 0 | 0 | 0 | 0 | 0 | 0 |
| August 2019 | 40 | 441.05 | 0 | 0 | 0 | 27 | 3.11 | 0 | 0 | 0 | 0 | 0 | 0 |
| September 2019 | 1,800 | 576.28 | 0 | 0 | 0 | 24 | 2.76 | 0 | 0 | 0 | 0 | 0 | 0 |
| October 2019 | 0 | 441.22 | 0 | 0 | 0 | 25 | 2.88 | 0 | 0 | 0 | 0 | 0 | 0 |
| November 2019 | 1,600 | 451.57 | 0 | 0 | 0 | 26 | 3.00 | 0 | 0 | 0 | 0 | 0 | 0 |
| December 2019 | 1,009 | 488.13 | 0 | 0 | 0 | 24 | 2.76 | 0 | 0 | 0 | 0 | 0 | 0 |
| January 2020 | 0 | 388.20 | 0 | 0 | 0 | 23 | 2.65 | 0 | 0 | 0 | 0 | 0 | 0 |
| February 2020 | 4,525 | 372.97 | 0 | 0 | 0 | 24 | 2.76 | 0 | 0 | 0 | 0 | 0 | 0 |
| March 2020 | 1,200 | 351.71 | 0 | 0 | 0 | 27 | 3.11 | 0 | 0 | 0 | 0 | 0 | 0 |
| April 2020 | 0 | 363.92 | 0 | 0 | 0 | 21 | 2.42 | 0 | 0 | 0 | 0 | 0 | 0 |
| May 2020 | 800 | 294.36 | 0 | 0 | 0 | 25 | 2.88 | 0 | 0 | 0 | 0 | 0 | 0 |
| June 2020 | 0 | 347.23 | 0 | 0 | 0 | 25 | 2.88 | 0 | 0 | 0 | 0 | 0 | 0 |
| July 2020 | 200 | 852.07 | 0 | 0 | 0 | 26 | 3.00 | 0 | 0 | 0 | 0 | 0 | 0 |
| August 2020 | 0 | 700.25 | 0 | 1.20 | 0 | 25 | 2.88 | 0 | 0 | 0 | 0 | 0 | 0 |
| September 2020 | 400 | 579.64 | 0 | 5.31 | 0 | 26 | 3.00 | 0 | 0 | 0 | 0 | 0 | 0 |
| October 2020 | 0 | 840.75 | 0 | 5.83 | 0 | 24 | 2.76 | 0 | 0 | 0 | 0 | 0 | 0 |
| November 2020 | 0 | 688.20 | 0 | 0.80 | 0 | 25 | 2.88 | 0 | 0 | 0 | 0 | 0 | 0 |
| December 2020 | 766 | 685.47 | 0 | 0 | 0 | 25 | 2.88 | 0 | 0 | 0 | 0 | 0 | 0 |
| January 2021 | 1,800 | 634.00 | 0 | 0 | 0 | 25 | 2.88 | 0 | 0 | 0 | 0 | 0 | 0 |
| February 2021 | 6,120 | 377.72 | 0 | 0 | 0 | 21 | 2.42 | 0 | 0 | 0 | 0 | 0 | 0 |
| March 2021 | 6,000 | 325.21 | 0 | 0 | 0 | 27 | 3.11 | 0 | 0 | 0 | 0 | 0 | 0 |

| Month | Chemical Waste | Waste Generated from Pretreatment Process | | | | General Refuse | | | | | | | |
|----------------|----------------|---|---------------------|---|-----------------------|--|-------------------|---------------------|-------------------|---|-------------------|-----------------------|-------------------|
| | | Disposed of at Landfill (see Note 1) | Metals (see Note 2) | Paper/ cardboard packaging (see Note 2) | Plastics (see Note 3) | Disposed of at Landfill (see Note 1 & 4) | | Metals (see Note 2) | | Paper/ cardboard packaging (see Note 2) | | Plastics (see Note 3) | |
| | | Litre | tonne | tonne | tonne | tonne | No. of collection | tonne | No. of collection | tonne | No. of collection | tonne | No. of collection |
| April 2021 | 9,700 | 651.29 | 0 | 0 | 0 | 22 | 2.53 | 0 | 0 | 0 | 0 | 0 | 0 |
| May 2021 | 4,000 | 671.03 | 0 | 0 | 0 | 24 | 2.76 | 0 | 0 | 0 | 0 | 0 | 0 |
| June 2021 | 0 | 558.72 | 0 | 0 | 0 | 25 | 2.88 | 0 | 0 | 0 | 0 | 0 | 0 |
| July 2021 | 0 | 382.74 | 0 | 0 | 0 | 26 | 3.00 | 0 | 0 | 0 | 0 | 0 | 0 |
| August 2021 | 3,420 | 687.05 | 0 | 0 | 0 | 26 | 3.00 | 0 | 0 | 0 | 0 | 0 | 0 |
| September 2021 | 2,400 | 304.01 | 0 | 0 | 0 | 25 | 2.88 | 0 | 0 | 0 | 0 | 0 | 0 |
| October 2021 | 0 | 342.38 | 0 | 0 | 0 | 23 | 2.65 | 0 | 0 | 0 | 0 | 0 | 0 |
| November 2021 | 2,000 | 394.26 | 0 | 0 | 0 | 26 | 3.00 | 0 | 0 | 0 | 0 | 0 | 0 |
| December 2021 | 0 | 392.44 | 0 | 0.67 | 0 | 22.00 | 2.53 | 0 | 0 | 0 | 0 | 0 | 0 |
| Total | 49,980 | 17,025.80 | 0 | 13.81 | 0 | 837.00 | 93.66 | 0 | 0 | 0 | 0 | 1 | 0.39 |

Notes:

1. General refuse was disposed of at NENT by subcontractors.
2. Metal and paper/cardboard packaging were collected by recycler for recycling.
3. Plastics refer to plastic bottles/containers, plastic sheets/foam from packaging material collected by recycler for recycling.
4. It was assumed that four 240-litre bins filled with 80% of general refuse were collected at each collection. The general refuse density was assumed to be around 0.15 kg/L.

Annex E

Environmental Complaint,
Environmental Summons
and Persecution Log

Annex E Cumulative Complaint and Summons/Prosecutions Log

| Reporting Month | Number of Complaints in Reporting Month | Number of Summons/Prosecutions in Reporting Month |
|------------------------|--|--|
| May 2015 | 0 | 0 |
| June 2015 | 0 | 0 |
| July 2015 | 0 | 0 |
| August 2015 | 0 | 0 |
| September 2015 | 0 | 0 |
| October 2015 | 0 | 0 |
| November 2015 | 0 | 0 |
| December 2015 | 0 | 0 |
| January 2016 | 0 | 0 |
| February 2016 | 0 | 0 |
| March 2016 | 0 | 0 |
| April 2016 | 0 | 0 |
| May 2016 | 0 | 0 |
| June 2016 | 0 | 0 |
| July 2016 | 0 | 0 |
| August 2016 | 0 | 0 |
| September 2016 | 0 | 0 |
| October 2016 | 0 | 0 |

| Reporting Month | Number of Complaints in Reporting Month | Number of Summons/Prosecutions in Reporting Month |
|------------------------|--|--|
| November 2016 | 0 | 0 |
| December 2016 | 0 | 0 |
| January 2017 | 0 | 0 |
| February 2017 | 0 | 0 |
| March 2017 | 0 | 0 |
| April 2017 | 0 | 0 |
| May 2017 | 0 | 0 |
| June 2017 | 0 | 0 |
| July 2017 | 0 | 0 |
| August 2017 | 0 | 0 |
| September 2017 | 0 | 0 |
| October 2017 | 0 | 0 |
| November 2017 | 0 | 0 |
| December 2017 | 0 | 0 |
| January 2018 | 0 | 0 |
| February 2018 | 0 | 0 |
| March 2018 | 0 | 0 |
| April 2018 | 0 | 0 |
| May 2018 | 0 | 0 |
| June 2018 | 0 | 0 |

| Reporting Month | Number of Complaints in Reporting Month | Number of Summons/Prosecutions in Reporting Month |
|------------------------|--|--|
| July 2018 | 0 | 0 |
| August 2018 | 0 | 0 |
| September 2018 | 1 | 0 |
| October 2018 | 0 | 0 |
| November 2018 | 0 | 0 |
| December 2018 | 0 | 0 |
| January 2019 | 0 | 0 |
| February 2019 | 0 | 0 |
| March 2019 | 0 | 0 |
| April 2019 | 0 | 0 |
| May 2019 | 0 | 0 |
| June 2019 | 0 | 0 |
| July 2019 | 0 | 0 |
| August 2019 | 0 | 0 |
| September 2019 | 0 | 0 |
| October 2019 | 0 | 0 |
| November 2019 | 0 | 0 |
| December 2019 | 0 | 0 |
| January 2020 | 0 | 0 |
| February 2020 | 0 | 0 |

| Reporting Month | Number of Complaints in Reporting Month | Number of Summons/Prosecutions in Reporting Month |
|------------------------|--|--|
| March 2020 | 0 | 0 |
| April 2020 | 0 | 0 |
| May 2020 | 0 | 0 |
| June 2020 | 0 | 0 |
| July 2020 | 0 | 0 |
| August 2020 | 0 | 0 |
| September 2020 | 0 | 0 |
| October 2020 | 0 | 0 |
| November 2020 | 0 | 0 |
| December 2020 | 0 | 0 |
| January 2021 | 0 | 0 |
| February 2021 | 0 | 0 |
| March 2021 | 0 | 0 |
| April 2021 | 0 | 0 |
| May 2021 | 0 | 0 |
| June 2021 | 0 | 0 |
| July 2021 | 0 | 0 |
| August 2021 | 0 | 0 |
| September 2021 | 0 | 0 |
| October 2021 | 0 | 0 |

| Reporting Month | Number of Complaints in Reporting Month | Number of Summons/Prosecutions in Reporting Month |
|------------------------|--|--|
| November 2021 | 0 | 0 |
| December 2021 | 0 | 0 |
| Overall Total | 1 | 0 |

Annex F

Investigation Report

Investigation Report of CEMS Exceedances

| | |
|--------------------------------------|---|
| Date | 1 - 31 December 2021 |
| Time | Continuous monitoring throughout December 2021 |
| Monitoring Location | Continuous Environmental Monitoring System (CEMS) |
| Parameter | Various emission parameters of the Cogeneration Units (CHP) and the Ammonia Stripping Plant (ASP) |
| Exceedance Description | <p>1. Continuous monitoring was carried out at the CAPCS, CHP and ASP throughout the reporting period using the CEMS. According to the EM&A Manual, exceedance is considered if the emission concentration of the concerned pollutants is higher than the emission limits stated in Tables 2.2, 2.3 and 2.5 of the EM&A Manual (Version F) for CAPCS, CHP and ASP respectively. The concentration of the concerned air pollutants were monitored on-line by the CEMS. Exceedances of various emission parameters were recorded on the CEMS including:</p> <ul style="list-style-type: none"> • SO₂ in CHP 3 • NO_x, SO₂, VOCs and NH₃ in the ASP <p>2. The Contractor has investigated the cause of the exceedance and identified that</p> <ul style="list-style-type: none"> • SO₂ exceedances from CHP 3 and the ASP were due to blockage of the hot water system of the desulphurisation system. • NO_x, VOCs and NH₃ exceedances from the ASP were due to system instability caused by blockage of the stripping columns of the ASP. |
| Action Taken / Action to be Taken | <p>The Contractor cleaned the blockage of the hot water system of the desulphurisation system immediately to resolve the issue.</p> <p>To ensure stripping efficiency and stable operation of the ASP, the Contractor has arranged acid-cleaning of the column. The Contractor has also arranged packaging cleaning in the next reporting month. The Contractor plans to arrange packaging cleaning in the coming reporting periods.</p> |
| Remedial Works and Follow-up Actions | <p>The Contractor is recommended to closely monitor the processes, including the modification works and follow-up emission monitoring of the ASP to avoid exceedance.</p> <p>The Contractor should review the routine inspection and maintenance schedule of the ASP and conduct preventative maintenance to avoid similar re-occurrence of the equipment failure.</p> |

Prepared by: Angela Yung, MT Representative

Date: 11 January 2022

Investigation Report of Effluent Discharge Exceedances

| | |
|--------------------------------------|--|
| Date | 9 December 2021 |
| Monitoring Location | Petrol Interceptor 2 (Stream B) |
| Parameter | Various discharge parameters of the Petrol Interceptor 2 |
| Exceedance Description | <p>1. According to the EM&A Manual (Rev. F), the monitoring should be carried out in accordance with the Water Pollution Control Ordinance (WPCO) licence. The licence requires the Contactor to carry out bi-monthly sampling and monitoring at the Petrol Interceptors. Sampling is required for this reporting period. Sample collected from Petrol Interceptor 2 showed exceedance of various discharge limits:</p> <ul style="list-style-type: none"> • Suspended Solid • Chemical Oxygen Demand <p>2. The Contractor has investigated the cause of the exceedance and identified that:</p> <ul style="list-style-type: none"> • Ad-hoc unloading and unpacking of food waste (21 tonnes of egg, 10 tonnes of ginseng, etc.) arranged by EPD near the sampling point between mid-November and early December 2021. • During the period, cleaning water has washed food residue down to the petrol interceptor and might have contaminated the concerned sampling point. • The water level at the sampling point was low during sampling. There were limited water flow as the reporting period was a dry season. |
| Action Taken / Action to be Taken | The Contractor has arranged cleaning of the petrol interceptor in January 2022. |
| Remedial Works and Follow-up Actions | The Contractor will arrange routine cleaning right after ad-hoc works. |

Prepared by: Angela Yung, MT Representative

Date 14 January 2022

Investigation Report of Foam Overflow and Leakage from the Anammox Pilot Plant

| | |
|--------------------------------------|---|
| Date | 23, 28 and 29 December 2021 |
| Incident Description | <p>Foam overflow from tanks to surface channel from the Anammox Pilot Plant was reported on 23 and 28 December 2021. The Contractor found no discharge to the nearby channel on 23 and 28 December 2021.</p> <p>Wastewater leakage from a loosen flexible pipe of the Anammox Pilot Plant was reported on 29 December 2021.</p> |
| Action Taken / Action to be Taken | The leakage on 29 December 2021 was intercepted and wastewater was diverted to the wastewater treatment system. |
| Remedial Works and Follow-up Actions | <p>A containment bund has been constructed around the pilot plant to contain any future spillages. Communication channel between site and plot operator has been established for immediate control actions in the case of spillage.</p>  |

Prepared by: Angela Yung, MT Representative

Date 22 August 2022